

2016 TOWN OF WAUSAU ROAD PROJECTS

Budgeted Amount	Miles Approved	Estimated Costs	Miles Completed	Estimated Costs
Crack filling	3.94	\$ 51,897.00	3.94	\$ 51,897.00
Slag Seal Coat	1.96	\$ 33,767.00	1.96	\$ 33,767.00
Chip Seal	3.59	\$ 70,457.00	1.63	\$ 31,990.00
Chip Seal w/ patching	1.21	\$ 25,000.00	1.1	\$ 25,000.00
Double Chip Seal	0.37	\$ 14,523.00	0.37	\$ 14,523.00
Granite Lifts	2.7	\$ 27,700.00	3.09	\$ 30,000.00
Reconstruct	1.1	\$ 186,471.00	1.1	\$ 186,471.00
	14.87	\$ 409,815.00	13.19	\$ 373,648.00
			Culverts	\$ 9,586.47
			Estimated cost of roads not chip sealed*	\$ 26,580.53
Completed Road Projects	Distance (Miles)			
E Hamilton St	0.31	Crackfilled		\$ 409,815.00
Granite Rd	1.63	Crackfilled		
McIntosh St	2	Crackfilled		
E Troy St	1.1	Crackfilled & Chipsealed		
Business Park Dr	0.29	Crackfilled & Chipsealed		
N 33rd St	0.25	Crackfilled & Chipsealed		
N 65th St	1.09	Crackfilled & Chipsealed		
Tower Rd	1.96	Crackfilled & Slag Sealed		
35th St , Dunbar & 36th St	0.37	Double Chip Sealed		
85th St	1.1	Reconstruct		
E Jefferson	0.5	3" Granite Lift		
Lori -Jodi Lane	0.2	3" Granite Lift		
73rd @ E Jefferson	0.25	5" Granite Lift		
73rd @ Tower	0.29	4" Granite Lift		
69th @ E Jefferson	0.29	4" Granite Lift		
Butternut Rd E of 69th	0.29	3" Granite Lift		
93rd @ Meadow Lane	0.24	3" Granite Lift		
Pioneer Lane	0.13	3" Granite Lift		
49th St	0.26	3" Granite Lift		
James St	0.1	3" Granite Lift		
Michael St	0.1	3" Granite Lift		
Frank St	0.1	3" Granite Lift		
Highland St	0.34	3" Granite Lift		
Total Miles of Roads	13.19			

*Two roads were not able to be chip sealed due to the roads requiring more work than anticipated.